

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Kaiser-Francis

Complete Address: 909 Palace Bldg., Tulsa, Oklahoma 74103

Lease Name Christiansen "C" Well No. # 1

Location C NE Sec. 18 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3604'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling Inc.

Address: 912 Central Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 2:00 PM Day 24th Month April Year 1965

The Above well was plugged as follows:

273' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid
level was up in the hole. 1st cementing plug and 1/4 sack of hulls was
pushed in fluid to 265', and cemented with 25 sacks, through the drill
pipe. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged solid with hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 4/26/65
INV. NO. 1046-u

Signed: Archie Elving
Well Plugging Supervisor