

15-185-20071-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1967
11-27-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed November 13, 1967.

Operator's Full Name L. K. Parrish

Complete Address: 714 Fourth National Bank Bldg., Wichita, Kansas 67202

Lease Name Christiansen Well No. # 3

Location SW NE NW Sec. 18 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3630'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Burt Drilling Company

Address: 1823 Washington, Great Bend, Kansas 67530 License No.

Operation Completed: Hour 5:00PM Day 22nd Month November Year 1967

The Above well was plugged as follows:

278' of 8 5/8" surface pipe, cement circulated with 240 sacks. Fluid level
in the hole was at 165'. 1st cementing plug and 1/4 sack of hulls was pushed in
fluid to 250', and cemented with 25 sacks, through the drill pipe, with cement
from 250' to 175'. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks,
with cement from 30' to the base of the cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED
DATE 11-28-67
INV. NO. 6768-W