



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Carl W. Boxberger

Complete Address Box 474 Great Bend, KS

Lease Name Christiansen Well No. 1

Location SE/NE/NE Sec. 18 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3613

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering Inc

Address Box 698 Great Bend, KS License No. 670

Operation Completed: Hour 2:30 PM Day 17 Month 10 Year 1974

The above well was plugged as follows:

250 ft 8 5/8 surface cement circulated. 3613 ft 4 1/2 long string
cemented with 100 sacks. Top perf. 3255 ft. Sand to 3200 ft, 4
sacks cement with bailer. Pulled 2000 ft 4 1/2. Pump 2 sacks hulls,
10 sacks gel, 100 sacks cement to surface.

Pumped by Allied Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

Signed: *Russell E. Christian*
Well Plugging Supervisor

INVOICED

DATE 10/23/74

INV. NO. 148-W