

15.185.13074.0000

Form CP-3
Rev. 6-26-62

KANSAS

SP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Well Plugging Authority,
original issued August 21, 1967
renewal issued November 30, 1967

RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management, Inc.

Complete Address: Box 922, Great Bend, Kansas 67530

Lease Name Fisher Well No. # 4

Location NE SE SW Sec. 19 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3615'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Russ Casing Pulling, Inc.

Address: Box 1082, Great Bend, Kansas 67530 License No. 623

Operation Completed: Hour 2:00PM Day 20th Month February Year 1968

The Above well was plugged as follows:

297' of 8 5/8" surface pipe, cemented with 325 sacks. 3605' of 5 1/2" long string,
cemented with 125 sacks. Top perforation 3283'. Bottom of the hole was sanded
to 3250', and cemented with 5 sacks, through the dump bailer, with cement from
3250' to 3210'. Bridge plug was pushed in fluid to 280', bridge plug and rock
bridge from 280' to 270'. 8 sacks of cement with 8% Calcium Chloride was mixed
in a barrel, and put on plug at 270', through the dump bailer, and let set for
3 hours. Hole was bailed dry, and cemented with 4 yards of ready-mix cement,
with cement from 270' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audine Elving
Well Plugging Supervisor

DATE 2/21/68

INV. NO. 7296-W