

R
KANSAS

15-185-13073.0000

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1967
11-29-67
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued August 21, 1967.

Operator's Full Name Petroleum Management, Inc.

Complete Address: Box 922, Great Bend, Kansas 67530

Lease Name Fisher Well No. # 3

Location C N/2 NE SW Sec. 19 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3619'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Midway Drilling, Inc.

Address: Box 921, Great Bend, Kansas 67530 License No. 620

Operation Completed: Hour 12:00 PM Day 27th Month November Year 1967

The Above well was plugged as follows:

308' of 8 5/8" surface pipe, cemented with 325 sacks. 3607' of 5 1/2" long string,
no record of cement. Plug back T.D. 3500'. Top perforation 3312'. Bottom of the
hole was sanded to 3275', and cemented with 5 sacks, through the dump bailer.
2367' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in
fluid to 300', bridge plug and rock bridge from 300' to 290'. 5 sacks of cement
was mixed in a barrel, and put on plug at 290', through the dump bailer, and let
set for 2 weeks. Hole was bailed dry, and filled with 4 yards of ready-mix cement
with cement from 290' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11-29-67

INV. NO. 6789-W