

15.185.13071.0000

R

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 29 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Well Plugging Authority,  
issued August 21, 1967.

Operator's Full Name Petroleum Management, Inc.

Complete Address: Box 922, Great Bend, Kansas 67530

Lease Name Fisher Well No. # 1

Location SE NE SW Sec. 19 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3626'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Midway Drilling, Inc.

Address: Box 921, Great Bend, Kansas 67530 License No. 620

Operation Completed: Hour 11:30 Day 27th Month November Year 1967

The Above well was plugged as follows:

316' of 8 5/8" surface pipe, cemented with 325 sacks. 3584' of 5 1/2" long string,  
cemented with 300 sacks. Plug back T.D. 3549'. Top perforation 3042'. Iron in the  
at 1550'. Hole was sanded from 1550' to 1540', and cemented with 5 sacks, through  
the dump bailer, with cement from 1540' to 1500'. 1035' of 5 1/2" long string was  
recovered from the hole. Bridge plug was pushed in fluid to 300', bridge plug  
and rock bridge from 300' to 290'. 5 sacks of cement was mixed in a barrel, and  
put on plug at 290', through the dump bailer, and set from 2 weeks. Hole was  
bailed dry, and filled with 4 yards of ready-mix cement, with cement from 290'  
to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 11-29-67

INV. NO. 6790-W