

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Well Plugging Authority,
original issued August 21, 1967,
renewal issued November 30, 1967.

Operator's Full Name Petroleum Management, Inc.

Complete Address: Box 922, Great Bend, Kansas 67530

Lease Name Fisher Well No. # 2

Location SE NW SW Sec. 19 Twp. 21 Rge. 12 (E) (W)W

County Stafford Total Depth 3611'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Russ Casing Pulling, Inc.

Address: Box 1082, Great Bend, Kansas 67530 License No. 623

Operation Completed: Hour 2:45PM Day 20th Month February Year 1968

The Above well was plugged as follows:

306' of 9 5/8" surface pipe, cemented with 325 sacks. 3606' of 5 1/2" long string,
cemented with 300 sacks. Plug back T.D. 3560'. Top perforation 3532'. Bottom
of the hole was sanded to 3500', and cemented with 5 sacks, through the dump
bailer, with cement from 3500' to 3460'. 1818' of 5 1/2" long string was recovered
from the hole. Bridge plug was pushed in fluid to 290', bridge plug and rock
bridge from 290' to 280'. 8 sacks of cement with 8% Calcium Chloride was mixed
in a barrel, and put on plug at 280', through the dump bailer, and let set for
3 hours. Hole was bailed dry, and cemented with 4 yards of ready-mix, with
cement from 280' to the base of the cellar.
I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/21/68

INV. NO. 7295-W

Signed: Audie Elving
Well Plugging Supervisor