

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15185-10097.0002

LEASE NAME Sipes

WELL NUMBER #2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1980 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 21 TWP. 21 RGE. 13 (E) or (W)

COUNTY Stafford

LEASE OPERATOR Four-Way Operating, Inc.

ADDRESS Box 698, Great Bend, Kansas 67530

PHONE# (316-792-2506) OPERATORS LICENSE NO. 5310

Character of Well SWD

Date Well Completed 6-18-92

Plugging Commenced 10-2-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-7-92

The plugging proposal was approved on October 7, 1992 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? --- If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom T.D. 2100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	283'	None
				6"	2089'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Ran 2" tubing to 1900'. Howco plugged the well with 150 sacks 60/40 pozmix cement w/ 6% gel at 1900', 150 sacks cement at 915', 25 sacks cement at 700' and 75 sacks cement at 610'. Pulled tubing and found top of cement at 504' with SLM. 10-7-92 Ran tubing to 490'. Howco plugged well with 100 sacks cement circulated to surface. Pulled tubing and filled casing with 10 sacks cement. Job finished at 11:00 A.M.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Four-Way Operating, Inc. OCT 8 1992

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) Wichita, Kansas (for) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold

Box 698, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 7th day of October, 1992

Jana M. Leatherman
Notary Public

My Commission Expires:

STATE NOTARY PUBLIC
KANSAS
JANA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-95