

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Stafford County. Sec. 21 Twp. 21 Rge. (E) 13 (W) X

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SE/4 SW/4 NE/4 X

Lease Owner J.D. Ferrell Drilling Company, Inc. X

Lease Name Hoffman Well No. 1

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-17-48 19

Application for plugging filed 19 X

Application for plugging approved 19 X


Plugging commenced Sept 26, 1948 19

Plugging completed Oct 5, 1948 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well C. Stough

Producing formation Depth to top Bottom Total Depth of Well Feet X

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	3699.5	4 1/2"	5-17-48	2884' 1"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked bottom of hole. Run 6 cement.
Mudded hole to 215' of top. Run 15 sacks of cement.
Mudded hole to 40' of top. Run 10 sacks of cement.
Well Completed.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Ferrell Drilling Co, Inc.
Address Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.
J. W. Railsback (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Railsback

(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of Oct 1948
Merkel V. Sandefur Notary Public.

My commission expires Oct-15-1951



WELL LOG

J. D. Ferrell et al
Hoffman ST/₁

Sec 21 T.21 R 13W
990' DWL 330' NSL
SE/4 SW/4 NE/4
County: Stafford

Total Depth 3701'
Comm: 5-3-48 Comp: 5-17-48
Contractor: J. D. Ferrell Drig. Co.
Issued 5-20-48 Rotary O-3701

CASING:
3 5/8" 221' Cen.
4 1/2" 3699.5' Cen.

Elevation 1896'
Production:

cellar	4
surface soil	30
sand & gravel	71
hard shell pyrite	101
shale & shells	222
sticky shale & sand	460
red bed	762
anhydrite	783
shale & shells	1632
anhydrite lime	1675
shale & shells	1745
shale & lime	2040
shale & shells	2130
lime	2230
lime & shale	2300
shale & shells	2765
broken lime	2860
lime & shale	2970
broken lime	2985
lime & shale	3000
lime	3145
lime & shale	3160
lime	3225
lime & shale	3510
shale & sand	3355
lime	3473
soft white lime	3481
lime	3611
chert	3625
chert & lime	3650
sticky shale & sand	3701
Total Depth	3701

Tops

Anhydrite	762
Topoka	2955
Kansas City	3354
Base K C	3590
Conglomerate	3605
Viola	3614
Simpson	3651
Arbuckle	3699
T.D.	3701

We hereby certify this to be a correct and accurate log of the above described well as shown by the daily drilling reports.

J. D. FERRELL DRILLING COMPANY

By J. W. Ralston

Subscribed and sworn to before me this 24 day of May 1948

My commission expires:

10-15-51

Merl V. Sandefur
Notary Public

PLUGGING
WELL SEC 21 T 21 R 13W
BOOK PAGE 6 LINE 14

RECEIVED
Commission Div.
DEC - 8 1948
STATE REGISTRATION
COMMISSION
KANSAS