


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittler Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Stafford County. Sec. 21 Twp. 21 Rge. (E) 13 (W)  
Location as "NE/CNW/4SW/4" or footage from lines NW NW NW  
Lease Owner Westgate-Greenland Oil Company  
Lease Name Harter Well No. 2  
Office Address 1022 Union National Bank Building  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed January 24, 1950 19  
Application for plugging filed Orally January 24, 1950 19  
Application for plugging approved " " " 19  
Plugging commenced January 24, 1950 19  
Plugging completed January 24, 1950 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well C.D. Stough  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	296	9 5/8"	296	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3757 to 290 feet, set Halliburton plug @ 290 feet  
Run 20 sacks cement and filled hole with heavy mud to 39 feet, set Halliburton  
plug at 39 feet and ran 10 sacks cement to cellar base.

RECEIVED  
FEB 7 X 1950  
STATE CORPORATION COMMISSION  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Westgate-Greenland Oil Company c/o G. E. Bitler  
Address 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
G. E. Bitler (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *G. E. Bitler*  
1022 Union National Bank Building  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of February, 1950

*Esther Russell*

Notary Public.

My commission expires May 25, 1953



COMPANY: Westgate Greenland Oil Co.  
 CONTRACTOR: Jackson Drilling Corporation  
 FARM: Harter #2  
 LOCATION: NW NW NW Section 21-21-13  
 Stafford County, Kansas  
 ELEVATION: 1911  
 COMMENCED: January 12, 1950  
 COMPLETED: January 24, 1950

0	to	65	Sand
65	to	95	Pyrite
95	to	100	Pyrite & sand
100	to	220	Hard sand
220	to	445	Shale & shells
445	to	780	Red bed
780	to	810	Anhydrite
810	to	1270	Shale & shells
1270	to	1515	Salt & shale
1515	to	1540	Salt
1540	to	1670	Shale & shells
1670	to	2110	Lime & shale
2110	to	2200	Shale
2200	to	2340	Shale & shells
2340	to	2870	Shale & lime
2870	to	2940	Shale
2940	to	3210	Lime
3210	to	3270	Lime & shale
3270	to	3360	Shale
3360	to	3580	Lime
3580	to	3620	Shale
3620	to	3654	Viola
3654	to	3670	Simpson
3670	to	3705	Shale & lime
3705	to	3710	Arb.
3710	to	3718	Lime
3718	to	3757	Lime & shale
		3757 T.D.	

9 5/8" casing set at 296 feet - Cemented with 225 sacks cement and 2 sacks calcium chloride

Tops - Heeb. 3233  
 Lansing 3370  
 Cong. 3615  
 Viola 3628  
 Simpson 3646  
 Arbuckle 3698

**PLUGGING**  
 FILE SEC 21-21-13  
 WORK FACT 34 LINE 30

REC

Cons

FEB 7 X 1950

STATE

COMMISSION

MINN.S

Dry and Abandoned

All measurements from top of derrick floor

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Harter #2, Section 21-21-13, Stafford County, Kansas, as reflected by files of the Jackson Drilling Corporation.

*Clare A. Stewart*  
 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas, this 2nd day of February 1950.

*Dorothy J. Wilson*  
 Dorothy J. Wilson

My commission expires November 30, 1950