

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Stafford County, Sec. 21 Twp. 21S Rge. 13W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner Dizdar Petroleum Investment Co.

Lease Name Sipes Well No. 1

Office Address 309 S. Main, McAllen, Texas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 3, 1951 19

Application for plugging filed November 22, 1951 (verbal) 19

Application for plugging approved November 29, 1951 19

Plugging commenced November 22, 1951 19

Plugging completed November 27, 1951 19

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation lime Depth to top Bottom Total Depth of Well 3777 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	184'	
				4 1/2"	3776'	3700

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole plugged back from 3777 feet to 3700 feet with chat. Dumped 5 sacks of cement at 3700 feet. Shot off and pulled the 4-1/2 inch casing. Filled with mud to 184 feet. Set rock bridge and 15 sacks of cement at 184 feet. Filled with mud to 35 feet. Set bridge and 10 sacks of cement at the surface.

RECEIVED  
STATE CORPORATION COMMISSION

STAMPED  
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & L Casing Pulling Company

Address P. O. Box 508, Great Bend, Kansas

STATE OF TEXAS COUNTY OF HIDALGO, ss.  
MARKO DIZDAR (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Marko Dizdar

309 S. Main, McAllen, Texas (Address)

SUBSCRIBED AND SWORN TO before me this 29<sup>th</sup> day of August, 1952

Notary Public. Samuel L. Oakleaf

My commission expires 6/1/53

PLUGGING  
FILE SEC 21 T 21 R 132  
PAGE 127 LINE 16

SAMUEL L. OAKLEAF  
Notary Public, Hidalgo County, Texas

Company: Dizdar Petroleum Investment Co.  
Contractor: Dizdar & Nye Drilling Company  
Commenced: October 19, 1951  
Completed: November 3, 1951

Farm: Sipes # 1  
Location: SE SE SE Sec. 21-21-13W,  
Stafford County, Kansas  
Casing Record: 8 5/8" set at 184'  
4 1/2" set at 3776'

( Figures indicate bottoms)

Clay	45
sand	115
shale & shells	185
red bed and sand	380
red bed and sand	730
anhydrite	770
shale	980
shale & shells	1460
shale & lime	1700
lime & shale	1795
shale & lime	1855
lime & shale	1880
lime & shale	1895
lime & shale	2035
lime shale	2090
shale & shells	2195
shale & shells	2330
shale lime	2490
shale	2650
shale & shells	2755
shale	2855
lime & shale	2965
lime & shale	3055
lime shale	3150
lime & shale	3200
lime	3230
lime & shale	3280
lime & shale	3360
lime	3410
lime shale	3435
lime	3485
lime	3525
lime	3570
lime	3615
lime & shale	3665
lime & shale	3690
shale & lime	3711
lime	3716
lime	3723
shale	3732
lime	3775
lime	3777

K. C. 3365'

T. D.

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

DIZDAR & NYE DRILLING COMPANY

By James R. Nye

STATE OF KANSAS )  
                          ) SS  
ELLIS COUNTY      )

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 26 day of Aug, 1952

John L. Spies  
Notary Public

My Commission Expires, May 9, 1953

RECEIVED  
STATE CORPORATION COMMISSION

AUG 27 1952

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 21 T 21 R 132  
BOOK PAGE 127 LINE 16