


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 21 Twp. 21 Rge. 13 (E) (W) X
Location as "NE/CNW/SW" or footage from lines SE NW NE
Lease Owner Roward Supply Co. (Petroleum Inc.)
Lease Name Hoffman "A" Well No. #2
Office Address P.O. Box 897, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 4-21-66 19____
Application for plugging approved _____ 19____
Plugging commenced 4-23-66 19____
Plugging completed 4-26-66 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3672' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 3650', mixed and ran 5 sacks ^{Cement} thru dump bailer
Mudded hole to 285', set 10' rock bridge. Mixed and ran 5 sacks cement thru dump bailer.
Bailed hole down dry. Mixed and ran 20 sacks cement thru dump bailer. Mudded hole to 40' and set 10' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.C. Spencer
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of April, 19 66

My commission expires 24 October 1968

Sidney D. Miller
Notary Public.

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company - PETROLEUM, INC.
Farm - Hoffman No. 2

SEC. 21 T. 21 S. 13W
SE NW NE

Total Depth. 3679
Comm. 8-12-49 Comp. 8-27-49
Shot or Treated.
Contractor Jackson Drlg.
Issued. 2-4-50

County. Stafford
KANSAS



CASING:
8 5/8" 293' cemw/225 sx.
5 1/2" 3670' cem w/100 sx.

Elevation.

Production. Phys. 69 bbls.

Figures Indicate Bottom of Formations.

sand, clay	55
sand, iron	70
iron pyrite	80
shale, shells	215
sand	235
shale, shells	305
shale	405
red bed	570
shale	763
anhydrite	785
shale, shells, red bed	1115
shale, shells, salt	1260
shale, salt	1310
shale, shells	1640
lime	1985
shale sdy	2005
lime	2070
shale, shells	2150
lime, shale	2250
shale, shells	2655
lime, shale	2685
shale	2705
shaleshells	2780
lime, shale	2975
shale, shells	3065
lime	3256
lime, shale	3325
lime	3595
lime, some chert	3615
lime, shale	3665
arbuckle	3679
Total depth	

Tops:

Anhydrite	763
Heebner	3193
Toronto	3212
Brn lime	3318
Lansing	3332
Viola	3580
Simpson	3614
Arbuckle	3665

* Measurements from top of derrick floor.

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 - 1966
CONSERVATION DIVISION
Wichita, Kansas