

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

K.A.R.-82-3-117

15.185.10635.0000
API NUMBER 12-16-1949

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Hoffman
WELL NUMBER 3
330 Ft. from N Section Line
990 Ft. from E Section Line
SEC. 21 TWP. 21 RGE. 13
COUNTY Stafford
Date Well Completed 12-16-49
Plugging Commenced 11-5-97
Plugging Completed 11-11-97

LEASE OPERATOR GLM COMPANY
ADDRESS PO Box 193 Russell, KS. 67665
PHONE (785) 483-2123 OPERATORS LICENSE NO. 3134

Character of Well Oil
(Oil) Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on November 4, 1997 (date)
by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filled? NO If not, is well log attached? NO (Sent WITH CP 1)

Producing Formation Arbuckle Depth to Top 3351 Bottom 3365 T.D. 3365

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil & Water	3351	3365	8 5/8" 5 1/2"	323' 3351'	2414'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set Sanded to 3297'. Bailed 5 sks cement. Shot at 2537' & 2414'. Pulled to 750'. Pumped 8 gal/2 hulls and 50 sks cement displaced with 2 gal. Pulled to 350'. Pumped 2 hulls and 50 sks cement. Pulled to 60'. Circulated cement to surface with 40 sks cement. Pulled the rest of the pipe. Hole stayed full.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 249 Beth Drive Sterling, KS. 67579-9048

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GLM COMPANY
STATE OF Kansas COUNTY OF RUSSELL, ss.

TERRY E. MORRIS (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Terry E. Morris
(Address) P.O. Box 193 STATE RUSSELL, KS 67665

SUBSCRIBED AND SWORN TO before me this 27 day of January 1998 98

Ruby M Nowak Notary Public
My Commission Expires: 6-15-99

USE ONLY ONE SIDE OF EACH FORM

NOTARY PUBLIC - State of Kansas
RUBY M. NOWAK
My Appt. Exp. 6-15-99
Form CP-1 Revised 05-88