15.113.30163.0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

McPherson County. Sec. 5 Twp. 21S Rge. X (E) 5 (W)

Location as "NE/CNW¼SW¼" or footage from lines SW SW NW

Lease Owner John C. Graves, et al

Lease Name Peterson Well No. 1

Office Address 505 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 8, 1966

Application for plugging filed December 8, 1966

Application for plugging approved December 8, 1966

Plugging commenced December 8, 1966

Plugging completed December 8, 1966

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott, McPherson, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3374 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	205'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 200 feet. Followed by wooden plug and 1/4 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/4 sack hulls and 8 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 28 1966
12-28-1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.

Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF BUTLER, ss.

John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves

505 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of December, 19 66

Betty Brandt
Notary Public.

My commission expires April 30, 1967

15.113.30163.0000

R O T A R Y D R I L L E R S' L O G

OPERATOR: John C. Graves, et al
505 Union Center
Wichita, Kansas

DRILLING COMMENCED: December 2, 1966

CONTRACTOR: Graves Drilling Co., Inc.
505 Union Center
Wichita, Kansas

DRILLING COMPLETED: December 8, 1966

CASING RECORD: 7 Jts. 205' 8-5/8"
cemented with 175 sacks

LOCATION: Peterson No. 1
SW SW NW
Section 5-21S-5W
McPherson County, Kansas

- -

0	- 214	Soil & shale with lime
214	- 740	Shale
740	- 1066	Lime & shale streaks
1066	- 1660	Lime & shale
1660	- 2210	Shale & lime
2210	- 2595	Lime & shale
2595	- 2625	Shale & lime
2625	- 2670	Sand & sandy shale
2670	- 2712	Brown lime & shale
2712	- 2972	Lime
2972	- 3063	Lime & shale
3063	- 3290	Lime
3290	- 3332	Shale
3332	- 3337	Chert
3337	- 3344	Chat
3344	- 3374	Chert
	3374	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
DEC 28 1966
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John C. Graves
President

STATE OF KANSAS)
) SS:
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 12th of December, 1966.

Betty Brandt
Betty Brandt Notary Public

My commission expires:
April 30, 1967