

FEB 23 1996
2-23-1996
CONSERVATION DIVISION
WICHITA, KS N/A

15.185.01769.0000

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-185-97561 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR OXY USA INC. KCC LICENSE # 5447 ^{6/96}
(owner/company name) (operator's)

ADDRESS 110 S. Main #800 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-5624

LEASE PUNDACK WELL# 402 SEC. 29 T. 21S R. 13 (East/West)

-NE-SW-NW SPOT LOCATION/QQQQ COUNTY STAFFORD

1650 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8 SET AT 350' CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3711 CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: CIBP@3643' 1-KC 3400-3548

ELEVATION 1911 T.D. 3715 PBD 3643 ANHYDRITE DEPTH
(G.L. (K.B.)) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING As Per KCC Regulations

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Lance Fellhoelter PHONE# (316) 622-5630

ADDRESS 400 S. MAIN City/State Pratt KS 67142-1003

PLUGGING CONTRACTOR UNKNOWN AT THIS TIME KCC LICENSE # 510596
(company name) (contractor's)

ADDRESS PHONE # ()

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2/20/96 AUTHORIZED OPERATOR/AGENT: Stephen E. Danner
(signature)

11

WELL RECORD

Company Cities Service Oil Company Well No. 2 Farm Essmiller "B"
 Location 990' North and 990' East of W/4 Corner Sec. 29 T. 21 R. 13W
 Elevation 1911 (1909 Gr.) County Stafford State Kansas
 Drlg. Comm. September 14, 1951 Contractor Barbour Drilling Company
 Drlg. Comp. October 8, 1951 Acid None
 T. D. 3715' Initial Prod. Physical Potential: 461 oil, 0 water, 24 hrs. (10-12-51)

CASING RECORD:

8-5/8" @ 350' con. 250 ex cement
 5-1/2" @ 3711' con. 150 ex cement

FORMATION RECORD:

sand	0-85
iron & shale	180
shale & shells	351
red bed	385
shale & shells	1370
shale & lime	1785
lime	2035
lime & shale	2215
lime	2310
lime & shale	2615
shale & lime	2770
lime & shale	3025
lime	3715

3715 RTD = 3712 SIM
 lime 3715 T. D.

Drill stem test 3480-92, recovered
 1000' oil and 50' heavily oil-cut
 mud in 30 mins., gas in 10 mins.;
 B. H. P. 1220# in 15 mins.

Corr. Brown Limestone	3342'
Corr. Lansing	3355'
Corr. Conglomerate	3608'
Corr. Viola	3613'
Corr. Simpson	3653'
Corr. Arbuckle	3710'
Penetration	5'
Total Depth	3715'

Fillup:

450' oil in 45 mins.
 1265' oil in 1 hr. 35 mins.
 2350' oil in 3 hrs. 25 mins.
 3095' oil in 8 hrs. 45 mins.
 3210' oil in 12 hrs. 45 mins.

SYFO:	500'	2°
	1000'	1°
	1500'	0°
	2000'	1°
	2500'	1°
	3000'	0°
	3500'	1°

*not DDP
 - ...
 = sub*

RECEIVED
 KANSAS CORPORATION COMMISSION

FEB 23 1996

CONSERVATION DIVISION
 WICHITA, KS



15.185.01769.0000

Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Timothy E. McKee, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

February 26, 1996

OXY USA Inc
110 S Main #800
Wichita KS 67202

Pundsack #402
API 15-185-N/A
1650 FNL 990 FWL
Sec. 29-21S-13W
Stafford County

Dear Lance Fellhoelter,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760.