

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-185-22,861-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F.G. Holl Company, L.L.C. KCC LICENSE # 5056
(owner/company name) (operator's)
ADDRESS 9431 E. Central, Suite 100 CITY Wichita

STATE Kansas ZIP CODE 67206-2543 CONTACT PHONE # (316) 684-8481

LEASE KEELER "A" WELL# 1 SEC. 8 T. 21S R. 11 (East/West)

C - NW - SW - NW SPOT LOCATION/OOOO COUNTY Stafford

3630 FEET (in exact footage) FROM (S) N (circle one) LINE OF SECTION (NOT Lease Line)

4950 FEET (in exact footage) FROM (E) W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 260' KB CEMENTED WITH 225 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 3520' KB CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3454'-3456', 3444'-3448', 3428'-3436' Arbuckle

ELEVATION 1806' KB T.D. 3523' PBDT 3440' ANHYDRITE DEPTH 567'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, Hulls, cement and plug according to specifications.

RECEIVED
JUN 12 2003

(If additional space is needed attach separate page)

KCC WICHITA

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob Long PHONE# (620) 793-0195/(620) 786-5783(cell)

ADDRESS P.O. BOX 158 City/State Belpre, KS. 67519

PLUGGING CONTRACTOR Quality Well Service KCC LICENSE # 31925

ADDRESS 410 West Main, Lyson, KS. 67554 PHONE # 620) 727-3410
(company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 06/11/2003 AUTHORIZED OPERATOR/AGENT: Loveness Mpanje
(signature)

August 14, 1992

15.185.22861.0000

SAMPLE LOG -----Keeler "A" #1-8
Located: C-NW-SW-NW, Section 8, T21S-R11West, Stafford Co., Ks.

OPERATOR: F.G. Holl Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 7, 1992
COMPLETED: August 14, 1992

TOTAL DEPTH: 3523' K.B. Driller
3524' K.B. Logger

LOG

0' - 140' Surface Soil & Sand
140' - 265' Red Bed
265' - 1400' Shale
1400' - 3523 Shale & Lime

CASING RECORD

Spud at 7:30 a.m. 8-7-92. Drilled 265' of 12½" hole, Ran 6 joints of 8-5/8" 23# new casing. 248.23' set at 260' K.B. cemented with 225 sacks of 60x40 pozmix with 2% gel and 3% CC. Plug down at 11:30 a.m. 8-7-92 by HOWCO. Good returns to surface.

DEVIATION SURVEYS

1¼° - 3338'
½° - 3523'

Ran 86 joints of 5½" 14# casing. 3512.43' pipe set at 3520' (314.95 was used) K.B. cemented with 20 BBL of salt flush and 12 BBL of Super flush ahead of 50 sacks of lite cement, followed with 125 sacks of F.G. Holl mix. Plug down at 4:45 a.m. 8-14-92 by HOWCO. Centralizer on joints 1,4,7 & 10. Shoe joint is 16.75' long.

RECEIVED

JUN 12 2003

KCC WICHITA

NET DUE 30 DAYS AFTER RECEIPT. THANK-YOU.



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.
9431 E Central, Suite 100
Wichita, KS 67206

June 13, 2003

Re: KEELER A #1-8
API 15-185-22861-00-00
NWSWNW 8-21S-11W, 3630 FSL 4950 FEL
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888