

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,714-0000

LEASE NAME Schlochtermeyer

WELL NUMBER 1-7

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 7 TWP. 21S RGE. 11W (K) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 12-11-92

Plugging Completed 12-19-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G. Holl Company

ADDRESS P.O. Box 158 Belpre, Kansas 67519

PHONE#(316) 995-3171 OPERATORS LICENSE NO.

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3550'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	264'	none
				4 1/2"	3548'	1718'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 3375', ran 4 sacks cement. Shot pipe @2647', 1718'.

Pumped 300# hulls, 10 gel, 50 sacks cement, 10 gel, 100# hulls released
plug pumped 125 sacks cement 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) Kelso (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 30 day of December, 19 92

Irene Herzberg
Notary Public

My Commission Expires:



STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - SCHLOCHTEMEIER #1-7

Located: 150' N of SE SE SE, Section 7-21S-11W, Stafford
County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 5, 1990

COMPLETED: September 11, 1990

TOTAL DEPTH: 3550'

LOG

CASING RECORD

0 - 207 Surface Soil and Sand
 207 - 265 Red Beds
 265 - 610 Red Bed and Shale
 610 - 3470 Lime and Shale
 3470 - 3500 Arbuckle
 3500 - 3550 Lime and Shale

Ran 6 joints 8 5/8" casing. 251.15'
 pipe set at 264' K.B. Cemented with
 225 sacks 60/40 Pozmix with 2% gel
 and 3% cc. Plug down at 10:45 AM,
 9-5-90, by Howco.

Ran 101 joints 4 1/2" casing.
 3540.72' pipe set at 3548' K.B.
 Cemented with 20 bbl. salt flush,
 500 gal. super flush, 100 sacks
 Lite and 125 sacks F. G. Holl mix.
 Plug down at 7:30 AM, 9-11-90, by
 Howco.

RECEIVED
 KANSAS CORPORATION COMMISSION

JUN 22 1992

CONSERVATION DIVISION
WICHITA, KS

Deviation Surveys: 1° at 3045
 1 1/4° at 3429
 2° at 3500'

15185.22714.0000

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - SCHLOCHTEMEIER #1-7
 Located: 150' N of SE SE SE, Section 7-216-11W, Stafford
 County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 5, 1990

COMPLETED: September 11, 1990

TOTAL DEPTH: 3550'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 207 Surface Soil and Sand	Ran 6 joints 3 5/8" casing. 251.15' pipe set at 254' K.B. Cemented with 225 sacks 60/40 Pozmix with 2% gal and 3% cc. Plug down at 10:43 AM, 9-5-90, by Howco.
207 - 265 Red Beds	
265 - 610 Red Bed and Shale	
610 - 3470 Lime and Shale	
3470 - 3500 Arbuckle	
3500 - 3550 Lime and Shale	Ran 101 joints 4 1/2" casing. 3540.72' pipe set at 3548' K.B. Cemented with 20 bbl. salt flush, 500 gal. super flush, 100 sacks Lime and 125 sacks F. G. Holl mix. Plug down at 7:30 AM, 9-11-90, by Howco.

Deviation Surveys: 1° at 3045
 1 1/4° at 3429
 2° at 3500'