

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 138-36LOCATION SE-SW-22WSEC. 7 TWP. 21 RGE. 11WDry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2-A Lease J. SchleichermeyerOperator Magnolia Petroleum Co Address Box 570 - A. Beard - Mans.Field _____ County StaffordTotal Depth 3458 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4" 290 ft. Circulated with cement
5/8" casing set at 3449 ft. Taper Well Plug at 3250 ft
Filled with shot lead 3250 ft to 3230 ft. Dumped
4 sacks of cement at 3230 ft - Shot off & pulled the
3/4" casing - Filled with mud to 290 ft - Set Rock
Bridge & 15 sacks of cement at 290 ft - Mud to 30 ft
Bridge & 10 sacks of cement at the surface -
Bob Mullins - Plugging Contractor

RECEIVED

Conservation Div.

2-25-50

FEB 25 1950

PLUGGING

C. R. Stough -
District Conservation Agent

FILE SEC 7 T 21 R 11W
BOOK PAGE 138 LINE 36

Date 2-23-50