

15.185.00449.0000

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 28 1966  
7-28-66  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Duggan Well No. # 1

Location NE SW SW Sec. 30 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3578'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 10:30AM Day 27th Month July Year 1966

The Above well was plugged as follows:

240' of 8 5/8" surface pipe, cemented with 150 sacks. 3548' of 5 1/2" long string, cemented with 100 sacks. This is an open hole. Plug was pushed to 3400', 20' of rock, and cemented with 5 sacks. 2740' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 235', rock bridge from 235' to 225'. 2 sacks of Cal-Seal and 3 sacks of cement was mixed in a barrel, and put on plug at 225', through the dump bailer, and let set overnight. Next day hole was bailed dry, and 22 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 7/28/66  
INV. NO. 3643-10