

15.185.19530.0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
8-3-66
AUG 3 1966

CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Duggan Well No. # 4

Location NE NW SW Sec. 30 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3640'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 1:00PM Day 1st Month August Year 1966

The Above well was plugged as follows:

275' of 8 5/8" surface pipe, cemented with 275 sacks. 3640' of 4 1/2" long string, cemented with 375 sacks. Top perforation 3460'. Bottom of the hole was sanded to 3425', and cemented with 3 sacks. 2720' of 4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 270', rock bridge from 270' to 260'. 2 sacks of Cal-Seal was mixed in a barrel, and put on plug at 260', through the dump bailer, and let set over-week end. Hole was bailed dry, and 25 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 8/3/66
INV. NO. 3685-u