

15-009-20351-00-00

Form CP-3
Rev. 6-26-62

KANSAS

AP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Kathol Petroleum, Inc.

Complete Address: 900 Sutton Place, Wichita, Kansas

Lease Name Redetzke Well No. # 1

Location SE SW NE Sec. 4 Twp. 16 Rge. 13 (E) (W) W

County Russell Total Depth 3400

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Same (Co. tools)

Address: Same License No.

Operation Completed: Hour 8 PM Day 20 Month 2 Year 1969

The Above well was plugged as follows:

8 5/8" 221' Cwc.

Circulated hole with heavy mud to 650', set plug, & displaced 75 sax cement thru

drill pipe. Mud to 215' & displaced 20 sax cement thru drill pipe. Mud to 40 ',

1/2 sax hulls, plug, & displaced 10 sax cement with Sun Cementing Company's pump

truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Lawrence
Well Plugging Supervisor

INVOICED

DATE 2/25/69

INV. NO. 9345-W