


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines C SW NW SW
County. Sec. 3 Twp. 16S Rge. (E) 13W
Lease Owner Three G Oil, Inc.
Lease Name Maier Well No. 1
Office Address 1101 Wichita Plaza Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 31 19 68
Application for plugging filed Verbal Approval 19
Application for plugging approved Verbal Approval 19
Plugging commenced December 31 19 68
Plugging completed December 31 19 68
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 329' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,361 feet (total rotary depth) to 550 feet. Set bottom plug at 550 feet and cemented with 40 sacks of cement. Filled hole with heavy rotary mud to 300 feet. Set plug at 300 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented with 10 sacks cement, 2 sacks cement in rathole. Cementing service performed by Sun Oilwell Cementing, Inc. Pump Truck.

RECEIVED
STATE CORPORATION COMMISSION
JAN 8 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, INC.
Address 200 N. Main, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer
200 N. Main St., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of January, 19 68

My commission expires April 21, 1971
Martha Hartpence Notary Public.

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Three G Oil, Inc.

SEC. 3 T. 16S R. 13W

FARM Maier

NO. 1

LOC. C SW NW SW


15-009-20335-00-00

TOTAL DEPTH 3,361'
 COMM. December 20, 1968
 SHOT OR TREATED
 CONTRACTOR H-30, INC.
 ISSUED

COMP. December 31, 1968

COUNTY Barton
 KANSAS

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 8 1969
 CONSERVATION DIVISION
 Wichita, Kansas



CASINO

| | | | |
|----|--------|-------------------------------|-------------------|
| 20 | 10 | | |
| 15 | 8-5/8" | 329' cemented w/175 sx cement | ELEVATION 1892 KB |
| 12 | 6 | | |
| 13 | 5 | | |

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

| | | | |
|-----------------------------------|------|--------------------------|-------------|
| Surface Soil, Post Rock and Shale | 330 | <u>ELECTRIC LOG TOPS</u> | |
| Shale, Shells & Pyrite | 600 | Anhydrite | 842 + 1050 |
| Shale & Red Bed | 848 | Base Anhydrite | 873 + 1019 |
| Anhydrite | 877 | Topeka | 2783 - 891 |
| Shale | 1680 | Heebner | 3015 - 1123 |
| Shale & Lime Streaks | 1900 | Toronto | 3032 - 1140 |
| Shale & Lime | 2055 | Douglas | 3048 - 1156 |
| Lime | 2070 | Lansing | 3096 - 1204 |
| Lime & Shale | 2810 | Base K.C. | 3292 - 1400 |
| Lime | 3361 | Arbuckle | 3352 - 1460 |
| Rotary Total Depth | 3361 | Log T.D. | 3353 - 1461 |
| | | Rotary T.D. | 3361 - 1469 |

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer

 Arlo B. Romer

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 7th day of January, 1969.

Martha Hartpence

 Martha Hartpence - Notary Public

My Commission Expires:

April 21, 1971