

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-185-21539.0000

API NUMBER 15-185-21-539

LEASE NAME Brown

WELL NUMBER #1

SPOT LOCATION NW SW NW

SEC. 30 TWP. 21 RGE. 13 ~~XX~~ or ~~XX~~ West

COUNTY Stafford

Date Well Completed 1-26-82

Plugging Commenced 3-11-86

Plugging Completed 3-11-86

LEASE OPERATOR PV Properties, Inc.

ADDRESS 400 N. Woodlawn, Suite 101

PHONE # (316) 682-1537

OPERATORS LICENSE NO. 5030

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #1 Dodge City, KS

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Arbuckle Depth to top 3724' bottom 3728' T.D. 3734'

Show depth and thickness of all water, oil and gas formations.

DDTD 3750'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	210'	none
				4 1/2"	3728'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped down 4 1/2"; 2sx hulls, 25 sx cement, 5 sx gel, 30 sx cement, 5 sx gel, 1 sx hulls, wood plug, 140 sx cement. Hook up backside; pump 105 sx cement down backside.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. \_\_\_\_\_

Address Box 579 Great Bend, KS 67530

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


J. M. Vess (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) \_\_\_\_\_

J. M. Vess  
PV Properties, Inc.  
400 N. Woodlawn, #101

SUBSCRIBED AND SWORN TO before me this 14th day of March, 1986



Janis Panizzi  
Notary Public

My Commission expires: August 10, 1986

STATE CORPORATION COMMISSION

MAR 17 1986

Form CP-4  
Revised 01-84

DRILLERS WELL LOG

L. D. Drilling, Inc. - Contractor

P V Properties, Inc. - Operator

BROOK # 1  
 NW SW NW  
 Sec. 30-21-13  
 Stafford County, Ks.

T.D. 3733  
 Elev. 1922 K.B.

COMMENCED: 1-19-82  
 COMPLETED: 1-26-82

Casing

8 5/8" set at 210'  
 4 1/2" set at 3728'

Cement

W/175 sx. Common cement, 2% Gel 3% Cc  
 W/125 sx. Common, 10% Salt sat.  
 3/4 CFR 2

Formation

Hard sand  
 Sand  
 Red Bed  
 Anhy.  
 Shale & Shells  
 Shale  
 Lime & Shale

Depth

0 - 215  
 215 - 350  
 350 - 818  
 818 - 842  
 842 - 1135  
 1135 - 1575  
 1575 - 3733

FORMATION TOPS

Heebner	3253	(-1331)
Brown Lime	3376	(-1454)
Lansing K/C	3386	(-1464)
Arbuckle	3724	(-1802)

AFFIDAVIT

STATE OF KANSAS )  
 COUNTY OF BARTON ) ss

I certify that this is a true and correct copy of the above log to the best of my knowledge.

L. D. DRILLING, INC.

*L. D. Davis*  
 \_\_\_\_\_  
 L. D. Davis

Sworn to and subscribed before me this 30th day of January, 1982.

*Bessie M. DeWerff*  
 \_\_\_\_\_  
 Bessie M. DeWerff, Notary Public

My appointment expires: 5-20-85

