


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 30 Twp. 21 Rge. 13 (E) (W)

Location as "NE/CNW*SW*" or footage from lines SE NW NW

Lease Owner Spector Pipe and Supply Inc.

Lease Name Brown "C" Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 12-19-50 19__

Application for plugging filed Aug. 20, 1967 19__

Application for plugging approved Aug. 21, 1967 19__

Plugging commenced September 11, 1967 19__

Plugging completed September 14, 1967 19__

Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production. 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Arbuckle Depth to top 3721 Bottom 3770 Total Depth of Well 3771 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	197.30	none
				5 1/2" OD	3770	3005 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand to 3765 feet and dumped 5 sacks of cement.
Set a Rock Bridge at 200 feet and dumped 25 sacks of cement.
Mudded hole to 40 feet and dumped 10 sacks of cement.

SEP 25 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lynch Casing Pulling Company 457

Address R.F.D. 4, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

Spector Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 23th day of September, 19 67

Elsie Coady
Elsie Coady Notary Public.

My commission expires December 1, 1968



Specter Pipe & Sup.

15.185.01788.0000

OPY

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY PETROLEUM, INC.

SEC. 30 T. 21 R. 13W

FARM Brown "C"

NO. 1

LOC. SE NW NW

TOTAL DEPTH 3771

COUNTY Stafford

COMM. 12-8-50


COMP. 12-19-50

KANSAS

SHOT OR TREATED

CONTRACTOR Garvey Oil

ISSUED 2-17-51



CASING

8 5/8" 197.30

5 1/2" 3770

ELEVATION 1921 D.F.

PRODUCTION I.P.P. 451 bbls.
+ 12% wtr.

FIGURES INDICATE BOTTOM OF FORMATIONS

shale & shells	245
sand	320
sand & clay	345
red bed	812
anhyd.	836
shale & shells	1150
lime & shale	1700
lime	1800
lime & shale	1945
lime	2100
shale	2240
shale & shells	2390
shale	2686
shale & shells	2787
lime & shale	2905
lime	3134
shale	3358
shale & lime	3417
lime	3474
shale & lime	3678
shale	3719
lime	3771
Total Depth	

Tops:	
Anhyd.	812
Heebner	3251
Toronto	3270
Base Oread	3287
Brown lime	3371
Mansing	3382
Base Kansas City	3600
Penn. Basal Congl.	3630
Viola	3635
Simpson	3668
Arbuckle	3721

DST # 1 3386-3417 open 1 hr. 10 mins.
rec. 63' slightly oil cut mud.
D.S.T. # 2 3454-74 open 1 hr., rec. 30'
very heavily oil & gas cut mud / 360'
froggy oil
D.S.T. # 3 3478-3514, open 1 hr., rec
150' heavily oil & gas cut mud.

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1967
CONSERVATION DIVISION
Wichita, Kansas