

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County, Sec. 30 Twp. 21S Rge. (E) 13 (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines NE/4, 330' from Nth & West lines

Lease Owner Sinclair Oil & Gas Co

Lease Name J.W. Brown Estate

Well No. 1

Office Address Box 521, Tulsa, Okla

Character of Well (completed as Oil, Gas or Dry Hole) Oilwell

Date well completed July 22 1948

Application for plugging filed Sept 16 1952

Application for plugging approved Sept 18 1952

Plugging commenced Nov. 5 1952

Plugging completed Nov. 10 1952

Reason for abandonment of well or producing formation Production depleted

If a producing well is abandoned, date of last production Sept. 8 1952

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C.D. Stough

Producing formation Arbuckle Lime Depth to top 3732 Bottom Total Depth of Well 3739 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle Lime	dry	3732	3739	10-3/4"	426'	None
				7"	3766'	2486'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3739-3720' dumped sand
 3720-3690' cement 50 sx
 3690-300 mud
 300-290 rock bridge
 290-110 cement 10 sx
 110-25 Mud
 25-15 rock bridge
 15-0 cement 10 sx

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1952 11-19-1952

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr E.H. Gibbons

Address Box 551 Chase, Kans

STATE OF Kansas, COUNTY OF Rice, ss.

I, E.H. Gibbons (employee of owner) or (conservator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 551 Chase, Kans

(Address)

SUBSCRIBED AND SWORN to before me this 18th day of November, 1952

B. Ritterhouse
Notary Public.

My commission expires August 22, 1953

PLUGGING
FILE SEC 30 T 21 R 132
BOOK PAGE 45 LINE 21

Well Log
Sinclair Oil & Gas Co

J. W. Brown Estate #1
NE/4, 30-21S-13W
Stafford County, Kans.
Rig floor Elev. 1920

Drilling Contr.-Harbar Drlg Co
Began drilling 7/9/1948
Comp. drilling 7/22/1948
T.D. 3739' Arbuckle Lime
Initial potential 310' bbls oil
after 3,000 gals acid.

Drillers Log
Corrected to Surface Level

Sand	68'
Shale & Shells	413
Set 10-3/4" csg @ 413' w/225 sx	
Shale & Shells	438
Red Bed & Shells	593
Red Bed & Shale	783
Anhydrite	823
Shale & Shells	1593
Lime-Shale	1853
Lime	1983
Sand-Lime	1998
Lime-Shale	2123
Lime	2208
Lime-Shale	2393
Lime	2463
Lime-Shale	2690
Lime	2823
Lime-Shale	2888
Lime	2923
Lime-Shale	2983
Lime	3558
Lime-Chert	3598
Lime	3648
Chert-Lime	3678
Lime	3739-TD
Rotary tools to	3736'
Cable tools to	3739'
Top Conglomerate	3625'
Top Viola	3641'
Top Simpson	3673'
Top Arbuckle & 7" set at	3732'(125 sx cmt on 7" csg)

PLUGGING
FILE SEC-20 T-21S-13W
BOOK PAGE-45 LINE-31

RECORDED
STATE CONSERVATION COMMISSION
SEP 18 1952
CONSERVATION DIVISION
Wichita, Kansas