

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

STAFFORD County. Sec. 30 Twp. 21 Rge. 13 (X) (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW

Lease Owner PETROLEUM, INC.

Lease Name BROWN "C" Well No. 2

Office Address ROUTE 2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date well completed JANUARY 20, 19 51

Application for plugging filed MARCH 15, 19 62

Application for plugging approved MARCH 19, 19 62


Plugging commenced MARCH 20, 19 62

Plugging completed MARCH 24, 19 62

Reason for abandonment of well or producing formation DEPLETION OF PRODUCTIBLE FORMATIONS

If a producing well is abandoned, date of last production JANUARY 16, 19 62

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. LACKAMP, JR.

Producing formation KANSAS CITY Depth to top 3380' Bottom 3597' Total Depth of Well 3772 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
KANSAS CITY	WATER & LITTLE OIL	3561'	3565'	8-5/8" 5-1/2"	202 3771'	NONE 3084'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED BACK T.D. 3761'

FILLED HOLE WITH CURSHED ROCK FROM 3761' TO 3500'. PLACED 4 SACKS CEMENT ON TO CRUSHED ROCK. PULLED BOTTOM OF 5 1/2" CASING TO 340' AND PUMPED IN 10 SACKS MUD PLUS 30 SACKS CEMENT AT 340'. PULL 5 1/2" CASING TO 220' AND PUMP IN 30 SACKS CEMENT AT 220'. PULL 5 1/2" CASING TO 60' AND PUMP IN 30 SACKS CEMENT. PULL OUT CASING AND PLACE 4 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

APR 9 1962

CONSERVATION DIVISION
Wichita, Kansas

4-9-1962

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor MORGAN WELL PLUGGING SERVICE
Address 102 WEST 18TH STREET, HUTCHINSON, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

ROUTE 2, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 2ND day of APRIL, 19 62

My commission expires APRIL 14, 1963

Arthur J. Wiles Notary Public.



WELL LOG BROWN 'C' #2

Petrôleum, Inc., Lease Owner

Section 30, Twp. 21S, Rge. 13W

Garvey Oil, Contractor

Location: SW SW NW

Rotary Total Depth: 3772

County: Stafford County, Kansas

Commenced: January 2, 1951
Completed: January 15, 1951

Production: Arbuckle

Casing: 199' of 8 5/8"
3773.83' of 5 1/2"

Elevation: 1919 D.F.

Figures below indicate bottom of formation:

6	Cellar
100	Sand & Shale
115	Sand
135	Hard Sand
199	Shale & Shells
240	Shale
320	Soft Sand
785	Red Rock
837	Anhydrite
1395	Shale & Shells
1852	Lime & Shale
2010	Lime
2255	Shale & Shells
2840	Shale & Lime
3380	Shale
3416	Lime
3605	Shale
3665	Shale & Lime
3700	Shale
3722	Sand
3746	Arb. Lime
3772	R.T.D.

Tops:

3248	Heebner
3268	Toronto
3370	Br. Lime
3380	Lansing-K.C.
3597	B.K.C.
3625	P.B.C.
3629	Viola
3670	Simpson
3722	Arbuckle
DST #1	3383-16, rec. 90' watery mud.
DST #2	3432-76, rec. 180' water.
DST #3	3500-11, rec. 25' very slightly oil and gas cut mud. No BHP
DST #4	3516-50, rec. 250' gas, 130' heavily oil and gas cut mud, BHP 590#.
DST #5	3554-3600, rec. 510' gas, 90' heavily oil and gas cut mud. BHP 210#

RECEIVED
APR 9 1962
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

STATE OF KANSAS:
:
SEDGWICK COUNTY:

Eric H. Jager
Eric H. Jager

Subscribed to and sworn to before me, a Notary Public in said County and State this 22nd day of January, 1951.

Charlotte Heidman
Notary Public

My commission expires: 10-13-54