

STATE OF KANSAS
STATE CORPORATION COMMISSION
207 Colored Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.185.01773.0001
Well was completed on:

API NUMBER 9-21-1952

LEASE NAME Pundsack Unit

WELL NUMBER 407

2970 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 29 TWP. 21S RGE. 13 (E-W)

COUNTY Stafford

Date Well Completed 9-21-1952

Plugging Commenced 8-22-1989

Plugging Completed 8-23-1989

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE(S) (405) 749-2471 OPERATORS LICENSE NO. 5447

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 27, 1989 (date)

by Mr. Duane Rankin of District #1 (KCC District Agent's Name).

Well was completed on:
Is ACO-1 filed? 9-21-1952 if not, is well log attached? Yes

Producing Formation LKC Depth to Top 3490 Bottom 3556 T.D. 3716

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	Oil	3490	3556	8-5/8" 5-1/2"	361' 3712'	400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded back to 3490 & set 5 sx cmt on top of plug at 3440' Tied onto the 8-5/8" csg. & filled to surface using 5 sx gel, 175 sx 60/40 Poz. w/6% gel. State Witness: Mr. Duane Rankin

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Service Inc. License No. 9-1-1989

Address Oberlin, KS STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc. SEP - 1 1989

STATE OF Oklahoma COUNTY OF Oklahoma, ss. CONSERVATION DIVISION
Wichita, Kansas

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan Humphries

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 30th day of August, 1989

Margie G. Wilson
Notary Public

My Commission Expires: 4-1-92

WELL RECORD

15.185.01773.0000

Company Cities Service Oil Co. Well No. 7 Farm Essailer "B"
 Location 1550' West and 330' North of Center Sec. 29 T. 21 R. 13W
 Elevation 1911 (1909 Gr.) County Stafford State Kansas
 Drlg. Comm. September 3, 1952 Contractor Holm Drilling Company
 Drlg. Comp. September 21, 1952 Acid 380 gals. 9-23-52; 500 gals. 9-25-52
 T. D. 3716' Initial Prod. Physical Potential: 283 oil, 30 water, 24 hrs. (10-15-52)

CASING RECORD:

8-5/8" @ 361' cem. 250 sx cement
 5-1/2" @ 3712' cem. 150 sx cement

FORMATION RECORD:

clay & sand	0-97
iron & sand	121
sand	134
shale	362
shale & red bed	700
shale & shells	795
anhydrite	820
shale	1070
shale & shells	1435
shale	1600
lime & shale	1675
lime	1745
lime & shale	2225
shale & lime	2435
lime & shale	3065
lime	3224
lime & shale	3279
lime	3647
chert	3655
lime	3716

3716 RTD = 3714 SLM
 dolomite 3716 T. D.

Corr. Brown Limestone	3356'
Corr. Lansing	3368'
Corr. Viola	3623'
Corr. Simpson	3642'
Corr. Arbuckle	3711'
Penetration	5'
Total Depth	3716'

123' oil in 15 1/2 hrs.

9-23-52 Az. 500 gals., 380 gals. into formation in 15 hrs. at 1200#.

Cleaned out 1 1/2' to 3716'.

9-25-52 Set packer at 3696 and acidized 500 gals.

SYFO:	500'	1°
	1000'	1°
	1500'	0°
	2000'	1°
	2500'	0°
	3000'	0°
	3560'	1°

RECEIVED
 STATE CORPORATION COMMISSION

JUN 27 1989

CONSERVATION DIVISION
 Wichita, Kansas