

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County, Sec 29 Twp. 21 Rge. 13 (X) W (W)

Location as "NE/CNW4SW4" or footage from lines NW NW SW

Lease Owner Petroleum, Inc.

Lease Name Keller "B" Well No. 2

Office Address Route 2, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed April 8 1951

Application for plugging filed Sept. 18 1958

Application for plugging approved Sept. 19 1958

Plugging commenced Oct 1 1958

Plugging completed Oct. 3 1958

Reason for abandonment of well or producing formation Depletion of producible zones

If a producing well is abandoned, date of last production May 29 1958

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Froadfoot

Producing formation Arbuckle Depth to top 3719' Bottom ---- Total Depth of Well 3770 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	222'	None
				5 1/2"	3769'	2500'
Arbuckle	little oil and water	3719'	3724'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

(Plugged back to 3751')

Filled hole with crushed rock from 3751' to 3709' followed by 5 sacks cement. Mixed and pumped in 15 sacks gel followed by a plug and 75 sacks cement to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling, Inc.

Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Don Searle (employee of owner) or (~~agent~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

Route 2, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of October, 1958

[Signature]
Notary Public

STATE CORP. COMMISSION

My commission expires July 11, 1960

PLUGGING
FILE SEC 29 T. 21 R. 13W
BOOK PAGE 130 LINE 32

OCT 10 1958

CONSERVATION DIVISION
Wichita

10-10-1958

WELL LOG KELLER 'B' #2

Petroleum, Inc., Lease Owner Section 29, Twp. 21S, Rge. 13W

Garvey Oil, Contractor

Location: NW NW SW

Commenced: March 19, 1951

County: Stafford, Kansas

Completed: March 31, 1951

Production: Arbuckle

Rotary Total Depth: 3770'

Elevation: 1913 R.B.

Casing: 203' of 8 5/8"
3771.75' of 5 1/2"


Figures below indicate bottom of formation:

40	Surface Soil		
170	Sand & Gravel		
215	Shale & Shells		
280	Sand	3231	Heebner
335	Shale	3357	Brown Lime
790	Red Bed	3368	Lansing
825	Anhydrite	3625	Viola
1685	Shale & Shells	3665	Simpson
1834	Lime & Shale	3719	Arbuckle
2065	Lime		
2315	Lime & Shale		
2575	Shale & Shells	DST 3372-04,	open 1 hour, rec. 30' mud.
2647	Shale	DST 3410-62,	open 1 hour, rec. 55' mud.
2865	Shale & Shells	DST 3486-99,	open 1 hour, rec. 52' watery mud.
3015	Lime & Shale	DST 3720-23,	open 2 hours, rec. 62' heavily oil cut mud.
3255	Lime		
3360	Shale		
3625	Lime		
3666	Chert		
3687	Simpson		
3720	Shale		
3770	Lime		
3770'	R.T.D.		

PLUGGING
 FILE SEC. 29 T. 21 R. 13W
 BOOK PAGE 130 LINE 32

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.


 Eric H. Jager

STATE OF KANSAS:
 : SS.
 SEDGWICK COUNTY:

RECEIVED
 STATE OF KANSAS
 COMMISSION

Subscribed to and sworn to before me, a Notary Public in said County and State this 5th day of April, 1951.


 Charlotte Meilman
 Notary Public

My commission expires: 10-13-54