

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE-SE-SE

SEC. 21 TWP. 21 RGE. 13-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Sikes

Operator Digday Investment Co Address Box #647 G. Bend-Kan.

Field _____ County Stafford

Total Depth 3777 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/8 - 184 ft. Circulated with cement.
4 1/2" casing set at 3777 ft. 125 sacks of cement.
Plugged back to 3700 ft with chat. Dumped 5 sacks of
cement at 3700 ft. Shot off & pulled the 4 1/2" casing
used to 184 ft. Set Rock Bridge & 15 sacks of
cement at 184 ft. mud to 65 ft. Bridge &
10 sacks of cement at the surface.

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1951

11-29-51

C. W. Stoeck
District Conservation Agent

Date 11-27-51

PLUGGING
FILE SEC. 21 TWP. 21 RGE. 13-W
BOOK PAGE 127 LINE 12

[Handwritten mark]