

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
MAY 16 1967
CONSERVATION DIVISION
Wichita, Kansas

5-16-67

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued May 5, 1967.

Operator's Full Name Bovaird Supply Company

Complete Address: Box 897, Great Bend, Kansas 67530

Lease Name Hoffman "A" Well No. # 1

Location NW NW NE Sec. 21 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3676'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 12:00PM Day 15th Month May Year 1967

The Above well was plugged as follows:

317' of 8 5/8" surface pipe, cemented with 250 sacks. 3667' of 5 1/2" long string,
cemented with 100 sacks. This is an open hole. Bottom of the hole was sanded to
3650', and cemented with 5 sacks, through the dump bailer. 2803' of 5 1/2" long
string was recovered from the hole. Bridge plug was pushed in fluid to 220',
bridge plug and rock bridge from 220' to 210'. 4 sacks of cement was mixed in
a barrel, and put on plug at 210', through the dump bailer, and let set over-
week end. Hole was bailed dry, and 21 sacks of cement was added to the plug.

Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with
10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elving
Well Plugging Supervisor

DATE 5/16/67

INV. NO. 5231-W