
Form CP-3 Rev. 6-26-62

KANSAS STATE CORPORATION COMMISSION



J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas



JUL 15 1963

CONSERVATION DIVISION Wichita, Kansas

Openstonic Full Name	Dotmolou	T	,		, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	•
	Petroleu					
Complete Address:	352 N. Broadway,	Wichita,	Kansas			
Lease Name	Hoffman "A"	V	Vell No	# 4		
Location	HE NE KAKKKKE	Sec. 21	_Twp2]	l Rge. 13	_(E)_	_(W)_W
County	Stafford	Total	Depth	3730		
	X Gas Well Input					
Other well as hereaft	er indicated:					
Plugging Contractor:	Morgan We	ell Pluggi	ng Servi	Lce	 -	
Address: 102 W	. 18th St., Hutchir	son, Kans	as I	License No.	4	3
Operation Completed:	Hour 12:00PM Day 9t	h Month	July	Year	1963	
The Above well was pl	ngged as follows:					
3241 of 8 5/8"	surface pipe, cemer	t circula	ted with	1 225 sac	ks. 3	729'
of 5½" long str	ing, cemented with	100 sacks	. Top pe	erferatio	n 368	81,
Sanded to 3675'	, cemented with 5 s	acks. Flu	id level	l was up	in ho	le,
plug was set at	320', 10' rock bri	dge, ceme	nted thr	ough bai	ler w	ith
8 sacks, let se	t over night. Next	morning h	ole bail	Led down,	and	12
sacks was added	to plug. Hole was	filled wi	th mud t	50 401, 1	0' ro	ck
bridge, cemente	d with 10 sacks to	base cell	ar	, 		
3000' of 5½" lo	ng string recovered	from the	hole.	-		
	TNVOICED		ein state	d.	ع کا	U de la constanta
	INV. NO. 7415 - W	~		• ME E + 116	ouber	ATOOL (
•	1713 = 10	_				