

KANSAS

AL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 2 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name F.G. Holl

Complete Address 6427 E. Kellogg Wichita, Ks

Lease Name Keeler B Well No. 1

Location NW/SW/SW Sec. 8 Twp. 21S Rge. 11 (E) W

County Stafford Total Depth 3469

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers, Inc.

Address Box 486 Ellinwood, Ks License No. 462

Operation Completed: Hour 11:00 AM Day 29 Month 2 Year 1972

The above well was plugged as follows:

293 ft 8 5/8 surface pipe cement circulated. 3469 ft 4 1/2 long string
cemented with 75 sacks. Top perf. 3342 ft. Sand back to 3300 ft,
4 sacks cement with bailer. Pulled 2600 ft 4 1/2. Pump 2 sacks hulls,
15 sacks gel, 100 sacks cement to surface.

Pumped by Sun Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Russell B. Bihun*
Well Plugging Supervisor

DATE 3-3-72

INV. NO. 5273-12