

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-185-19529.0000 (of this well)

Operator's Full Name F.G.Holl.

Complete Address 6427 E. Kellogg, Wichita, Ks. 67207

Lease Name Scheufler "B" Well No. 1

Location NE NW NE Sec. 8 Twp. 21s Rge. 11 (E) (W) X

County Stafford Total Depth 3435

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Glenn's Casing Pulling.

Address Box 413-Ellingwood, Ks. 67526 License No. 832

Operation Completed: Hour 1 Pm. Day 30 Month 9 Year 1980

The above well was plugged as follows:

287' 8 5/8" casing w/200 sax cement. 4 1/2" casing set at 3435' w/600  
gal Latex-Top perforation at 3231'-Sand back to 3200'-Top sand w/4  
sax mixed cement w/dump bailer-Pull 2589' casing-Allied mixed & pumped  
in 8 5/8" casing 8 sax hulls-25 sax gel-125 sax 50/50 posmix cement  
w/4% gel & 3% cc to top of casing. Shut in w/500# pressure.

RECEIVED  
STATE CORPORATION COMMISSION

OCT - 2 1980

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
DATE 10-10-80  
INV. NO. 3309W