

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 185 - 30246 - 0000 (of this well)

Operator's Full Name F.G.Holl.

Complete Address 6427 E. Kellogg, Wichita, Ks. 67207

Lease Name Paul Scheufler Well No. 2

Location NW NE NE Sec. 8 Twp. 21 S Rge. 11 (E) (W) X

County Stafford Total Depth 3428

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Glenn's Casing Pulling.

Address Box 4732-Ellinwood, Ks. 67526 License No. 832

Operation Completed: Hour 11:45 Am Day 30 Month 9 Year 1980

The above well was plugged as follows:

297' 8 5/8" casing w/250 sax cement. 4 1/2" casing set at 3427' w/600
gal Latex. Preferated at 3340'-Sand back to 3300'-Top sand w/4 sax
mixed cement w/dump bailer. Pull 2505' casing. Allied mixed & pumped
in 8 5/8" casing 8 sax hulls-25 sax gel-125 sax 50/50 posmix cement
w/4% gel & 3% cc to top of casing. Shut in w/500# pressure.

RECEIVED
STATE CORPORATION COMMISSION

OCT - 2 1980

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 10-10-80
INV. NO. 3308-4