

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1963

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name Veeder Supply Co.Complete Address: Box 201, Cherryvale, KansasLease Name Peterson "A" Well No. # 1Location SE NW NE Sec. 6 Twp. 21 Rge. 11 (E) (W) WCounty Stafford Total Depth 3472Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Forbes Casing Pulling Co.Address: Box 221, Great Bend, Kansas License No. 49Operation Completed: Hour 9:30AM Day 21st Month August Year 1963

The Above well was plugged as follows:

261' of 8 5/8" surface pipe, cemented with 175 sacks. 3444' of 5 1/2" long
string, cemented with 100 sacks. Top perferation 3409'. Sanded to 3390',
cemented with 5 sacks. Fluid level in the hole was up, plug was pushed
to 260', 10' rock bridge, cemented with 5 sacks, mixed ⁱⁿ ~~through~~ the barrel
and put on the plug through the dump bailer, let set over night. Next
morning hole was bailed down and 15 sacks cement was added to the plug.
Hole was filled with mud to 40', 10' rock bridge, cemented with 10 sacks
to base cellar. 2686' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging SupervisorDATE 8/22/63INV. NO. 7634-W