

R

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 185 - 20,726.0000 (of this well)

Operator's Full Name Poor Boy Corporation

Complete Address Rt. #2 Ellingwood, Ks. 67526

Lease Name Dannebohm "B" Well No. 1

Location 150' SW NE NE NW Sec. 6 Twp. 21 SRge. 11 (E) (W) W

County Stafford Total Depth 3500

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Pipe Pullers, Inc.

Address Box 128, Ellinwood, Ks. 67526 License No. 462

Operation Completed: Hour 10:30 Am Day 31 Month 7 Year 1979

The above well was plugged as follows:

285' 8 5/8" casing w/225 sax cement. 4 1/2" casing set at 3498' w/125  
sax cement. Plug back to 3452'. Top pref. at 3429'-Sand back to 3400'.  
Top sand w/ 4 sax mixed cement w/ dump bailer. Pull 2701' 4 1/2" casing  
Sun mixed & pumped 8 sax hulls-25 sax gel-Release plug-Mixed & pumped  
100 sax 50/50 Posmix cement w/ 4% gel & 3% cc to top of casing. Shut  
in w/ 100# pressure.

RECEIVED  
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

8-2-79

INV. NO.

0129-W

AUG 2 1979  
8-2-79  
CONSERVATION DIVISION  
Wichita, Kansas

Signed:

[Signature]  
Well Plugging Supervisor