

State of Kansas



FORM - CP-2
Rev. 6-26-62

15.185.10636.0000

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bill Morgan of Morgan Well Plugging Serv. has this date requested permission to plug the following described well:

Mr. Morgan guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Hoffman "A" Well No. # 4

Location: SW NE NE Sec. 21 Twp. 21 Rge. 13(E)(W) W

County Stafford Total Depth 3730 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Morgan was instructed to plug the well as follows:

324' of 8 5/8" surface pipe, cement circulated with 225
sacks. 3729' of 5 1/2" long string, cemented with 100 sacks.
Top perforation 3688'. Sand to 3675', cement with 5 sacks.
Fill hole with mud to 240', 10' rock bridge, cement with
20 sacks. Fill hole with mud to 40'. 10' rock bridge, cement
with 10 sacks to base cellar.

Very truly yours,

Archie Elving
Conservation Division Agent