



15.113.30081.0060

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

November 29, 1964

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

DEC 7 1964  
12-7-64  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Bill Makely of Melland Drilling Co., Inc this  
date requested permission to plug the following described well:

Mr. Makely guarantees payment of the plugging fee.

Operator's full Name: Homer Krehbiel

Complete Address: Mc Pherson, Kansas

Lease Name: Schroeder Well No. 1

Location: SW SW SW Sec. 28 Twp. 21 Rge. 3 (D) (W) X

County Mc Pherson Total Depth 3557' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Makely was instructed to plug the well as follows:

Fill hole with mud to 300'. Push plug and 1/4 sack hulls to  
300' and cement hole with 20 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to  
40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent