

State of Kansas



FORM - CP-2
Rev. 6-26-62

15.185.01876.0000

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Jerry Young of Forbes Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Young guarantees payment of the plugging fee.

Operator's full Name: Veeder Supply Co.

Complete Address: Box 201, Cherryvale, Kansas

Lease Name: Peterson "A" Well No. # 1

Location: SE NW NE Sec. 6 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3472 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Young was instructed to plug the well as follows:

261' of 8 5/8" surface pipe, cemented with 175 sacks.

3444' of 5 1/2" long string, cemented with 100 sacks. Top

perferation 3409'. Sand to 3380', cement with 5 sacks.

Fill hole with mud to 260', 10' rock bridge, cement with

20 sacks. Fill hole with mud to 40', 10' rock bridge,
cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
Conservation Division Agent