

State of Kansas



15.185.20479.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Crawford of Red Tiger Drlg has this

date requested permission to plug the following described well:

Mr. Crawford guarantees payment of the plugging fee.Operator's full Name: Utica Southern Exploration IncComplete Address: 503 Mayo Bldg Tulsa, OKLease Name: Duggan Well No. 1Location: 70' N of NW/NW/SW Sec. 30 Twp. 21s Rge. 11 (E)(W) WCounty: Stafford Total Depth 3645 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Crawford was instructed to plug the well as follows:259 ft 8 5/8 surface cemented with 250 sacks. Pump plug.40 sacks cement to 500 ft. 2nd plug at 250 ft. with 25 sackscement. Mud to 40 ft, plug, 1/2 sack hulls, 15 sacks cementto surface. 2 sacks cement in rat hole.Pumped by Sun Cementing Co Great Bend, KS

Very truly yours,

Conservation Division Agent