



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Larry Curtis of Duke Drilling Company has this date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: Leo G. Wetherill Jr.

Complete Address: 2208 Power & Light Bldg., Kansas City 5, Mo.

Lease Name: Smith Estate Well No. # 21

Location: NE SE SE Sec. 16 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3469 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Curtis was instructed to plug the well as follows:

273' of 8 5/8" surface pipe, cemented with 300 sacks. Fill hole with drilling mud to 250', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent