

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-185-30260-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1966

3-23-66

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Larry Curtis of Duke Drilling Company has this date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: Leo G. Wetherill, Jr.

Complete Address: 2208 Power & Light Bldg., Kansas City, Missouri

Lease Name: Smith Estate Well No. # 24

Location: NW NE NW Sec. 16 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3500' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Curtis was instructed to plug the well as follows:

286' of 8 5/8" surface Pipe, cement circulated. Fill hole with drilling mud to 250', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving