



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 13 1962

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dec. 8, 1962

Dear Sir:

Mr. Cecil Olson of Duke Drilling Co. has this date requested permission to plug the following described well:

Mr. Cecil Olson guarantees payment of the plugging fee.

Operator's full Name: Leo G. Wetherill Jr.

Complete Address: 2208 Power & Light Bldg. Kansas, City, Mo.

Lease Name: Smith Estate # 12 Well No. # 12

Location: 150' W of SW-NW-NE Sec. 16 Twp. 21S Rge. 11 (E) (W) X

County Stafford County Total Depth 3500' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cecil Olson was instructed to plug the well as follows:

280' of 8 5/8" surface pipe circulated with cement. Hole filled to 240' with heavy drill mud, 1/2 sack hulls, 1st cementing plug and 20 sacks cement. Hole filled to 40' with heavy drill mud, 1/2 sack hulls, 2nd cementing plug and 10 sacks cement to base of cellar. Rat hole bridged and 2 sacks cement.

Very truly yours,

Herman J.ustus
 Conservation Division Agent