

State of Kansas



FORM - CP-2
Rev. 6-26-62

15.185.19533.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. L. O. Chubb of Duke Drilling Company has this date requested permission to plug the following described well:

Mr. Chubb guarantees payment of the plugging fee.

Operator's full Name: Leo G. Wetherill Jr.

Complete Address: 2208 Power & Light Bldg., Kansas City 5, Mo.

Lease Name: Smith Estate Well No. # 23

Location: NE SE SW Sec. 16 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3461 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Chubb was instructed to plug the well as follows:

278' of 8 5/8" surface pipe, cement circulated with 225 sacks.
Fill hole with drilling mud to 260', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving