

## DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
 Conservation Division  
 800 Bitting Building  
 Wichita, Kansas

FILE NO. 143-14LOCATION SW-SW-22ESEC. 16 TWP. 21 RGE. 11WDry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease C. P. Smith - "B"Operator Shull Oil Co Address Box #744 A. Bend. KansField \_\_\_\_\_ County StaffordTotal Depth 3457 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 7/8 - 225 ft. Circulated with cement.  
 4 1/2" casing set at 3446 ft. Plugged back to 3370 ft  
 with sand & chat - 10 bags of cement at 3370 ft.  
 Shot off & pulled the 4 1/2" casing. Filled with mud to 225 ft.  
 Set Rock Bridge & 15 sacks of cement at 225 ft -  
 Mud to 30 ft Plug & 10 sacks of cement at  
 the surface -

West Supply Co - Plugging Contractor -  
 3-31-50  
 MAR 31 1950

C. D. Stouffer  
 District Conservation Agent

Date 3-30-50