

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 3 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Abercrombie Drilling, Inc.

Complete Address: 801 Union Center, Wichita, Kansas

Lease Name Richardson Well No. # 1

Location NE NW SE Sec. 20 Twp. 21 Rge. 11 (E) W

County Stafford Total Depth 3539'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Vaughan Drilling, Inc.

Address: Box 825, Great Bend, Kansas License No.

Operation Completed: Hour 5:30 PM Day 31st Month August Year 1965

The Above well was plugged as follows:

246' of 8 5/8" surface pipe, cement circulated with 210 sacks. Fluid
level in the hole was at 75'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 225', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged and
cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/3/65
INV. NO. 1744-W

Signed: Archie Elving
Well Plugging Supervisor