

*VP*  
KANSAS  
STATE CORPORATION COMMISSION

15.185.10815.0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 12 1967

12-12-67

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued December 7, 1967.

Operator's Full Name Petroleum, Inc.

Complete Address: R. R. # 2, Great Bend, Kansas 67530

Lease Name Lincoln Well No. # 3

Location SE SW SE Sec. 29 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3810'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 1:00AM Day 11th Month December Year 1967

The Above well was plugged as follows:

233' of 8 5/8" surface pipe, cemented with 175 sacks. 3809' of 5 1/2" long string,  
cemented with 125 sacks. Plug back T.D. 3802'. Top perferation 3584'. Bottom  
of the hole was sanded to 3575', and cemented with 5 sacks, with cement from  
3575' to 3535'. 2955' of 5 1/2" long string was recovered from the hole. Hole was  
flowing with water and was squeezed. 15 sacks of Gel-Mud and 80 sacks of Pos-  
Mix cement was pumped into the surface pipe, through an 8 5/8" swage, to a  
pressure of 100 lbs., with cement from 240' to the base of the cellar.  
This cementing was done by Globe Cementing Company.

I hereby certify that the above well was plugged as herein stated.

Signed: *Audie Cluing*  
Well Plugging Supervisor

INVOICED

DATE 12/12/67  
INV. NO. 6879-W