

KANSAS

Y STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Alpine Drlg. Co. Inc.

Complete Address 800 Bitting Bldg. Wichita, Ks 67202

Lease Name Weirauch Well No. 1

Location C SW/NW Sec. 29 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3790

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Glenn & Smith Pipe Pulling Co.

Address 204 E. 6th Ellinwood, Ks License No. 396

Operation Completed: Hour 12:Noon Day 14 Month 7 Year 1970

The above well was plugged as follows:

248 ft of 8 5/8 surface pipe cemented with 250 sacks. 3785 ft of 5 1/2

long string cemented with 125 sacks. Top perf. 3759 ft-61 ft. Sand

to 3700 ft, 5 sacks cement with bailer. Pulled 1700 ft of 5 1/2.

Pumped 30 sacks Gel mud & 100 sacks cement to surface. Globe Cementing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Y Russell Bihertier*
Well Plugging Supervisor

DATE 7/16/70

INV. NO. 2238-W