

15.185.11695.0001

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
5-19-72
MAY 19 1972

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.

Complete Address Rt. 2 Great Bend, Ks

Lease Name Lincoln Well No. 4

Location SW/NE/SE Sec. 29 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3849

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering Co. Inc.

Address Box 698 Great Bend, Ks License No. 670

Operation Completed: Hour 12:noon Day 17 Month 5 Year 1972

The above well was plugged as follows:

279 ft 8 5/8 surface pipe cemented with 175 sacks. 3848 ft 5 1/2 long
string cemented with 100 sacks. Top perf. 3590 ft. Sand back to
3500 ft, 5 sacks cement with bailer. No pipe pulled. Pump 1 sack
hulls, 7 sacks gel., 50 sacks cement in 5 1/2. Pump 1 sack hulls,
7 sacks gel, 50 sacks cement in 8 5/8 to surface.

Pumped by Globe Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 5/19/72
INV. NO. 5726-W