

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-185-22,924.0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F. G. Holl Company, L.L.C. KCC LICENSE # 5056  
(owner/company name) (operator's)  
ADDRESS 6427 E. Kellogg P.O. Box 780167 CITY Wichita  
STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481

LEASE KEELER C WELL# 1-20 SEC. 20 T. 21S R. 11W (East/West)  
260' W & 30' N of  
N72 - NW - NW SPOT LOCATION/QQQQ COUNTY Stafford

300' FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)  
400' FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_  
CONDUCTOR CASING SIZE N/A SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS  
SURFACE CASING SIZE 8 5/8" SET AT 279' CEMENTED WITH 225 SACKS  
PRODUCTION CASING SIZE 5 1/2" SET AT 3594' CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3451' - 3461' Viola, 3477' - 3484' Simpson Sand  
ELEVATION 1783'/1792' T.D. 3600' PBTD 3581' ANHYDRITE DEPTH 532'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, Hulls, Cement and plug according to KCC regulations

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes  
If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:  
Rob Long PHONE# ( ) (620) 995-3171/(620) 793-0915(C)

ADDRESS P.O. BOX 158 City/State Belpre, Kansas 67519

PLUGGING CONTRACTOR Quality Well Service KCC LICENSE # 31925  
(company name) (contractor's)  
ADDRESS 401 West Main, Lyson, KS. 67554 PHONE # ( ) (620) 727-3410

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 03/2002

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 03/05/2002 AUTHORIZED OPERATOR/AGENT: Loveness Mpanje  
(signature)  
(Geologist)

RECEIVED  
MAR 07 2002  
3-7-02  
KCC WICHITA

X

6/02

6/02



## *Kansas Corporation Commission*

*Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### **NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Holl, F.G., Company L.L.C.  
6427 East Kellogg  
Wichita, KS 67207

March 08, 2002

Re: KEELER C #1-20  
API 15-185-22924-00-00  
N2NWNW 20-21S-11W, 300 FNL 400 FWL  
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

A handwritten signature in black ink, appearing to read "D. P. Williams".

David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888

## STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

FILE COPY

WELL LOG - - - - - KEELER "C" 1-20  
 Located: 260' W and 30' N of N/2 NW NW, Sec. 20-21S-11W,  
 Stafford County, Kansas

OWNER: F. G. Holl Company  
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 26, 1993  
 COMPLETED: September 1, 1993

TOTAL DEPTH: 3600'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 170 Surface Soil and Sand	Ran 6 joints 8 5/8", 23# casing. 267.21' pipe set at 279' K.B.
170 - 346 Red Bed	Cemented with 225 sacks 60/40 Pozmix, 2% gel and 3% cc. Plug down at 1:30 PM, 8-26-93, by Allied.
346 - 750 Red Shale	
750 - 1488 Shale	
1488 - 3600 Lime and Shale	Ran 88 joints 5 1/2", 14# new and used casing. 3585.16' pipe set at 3594' K.B. Cemented with 20 bbl salt flush and 500 gal. Superflush ahead of 100 sacks Lite cement, followed with 125 sacks F. G. Holl mix. Plug down at 10:45 PM, 9-1-93, by Howco.

Deviation Surveys: 1/2° at 285'  
 2° at 3252'  
 1 1/2° at 3600'

RECEIVED

MAR 07 2002

KCC WICHITA